



City of Portland, Oregon Bureau of Development Services Land Use Services

1900 SW 4th Avenue, Suite 5000 Portland, Oregon 97201 503-823-7300 Fax 503-823-5630 TTY 503-823-6868 www.portlandonline.com/bds

<u>-</u>

Date: March 3, 2009
To: Interested Person

From: Mieke Stekelenburg, Land Use Services

503-823-0669 / Mieke.Stekelenburg@ci.portland.or.us

NOTICE OF A TYPE I DECISION ON A PROPOSAL IN YOUR NEIGHBORHOOD

The Bureau of Development Services has approved a proposal in your neighborhood. The reasons for the decision are included in this notice. If you disagree with the decision, you can appeal it to the Oregon Land Use Board of Appeals (LUBA) at 550 Capitol St. NE, Suite 235, Salem, OR 97301. The phone number for LUBA is 1-503-373-1265. Information on how to appeal this decision is listed at the end of this notice.

CASE FILE NUMBER: LU 08-180500 LDP

GENERAL INFORMATION

Applicant/Owner: Prometheus Housing Group Llc

Charles Stone 211 NE Weidler St

Portland, OR 97232-1155

Site Address: 2006 N HUMBOLDT ST

Legal Description: LOT 1 BLOCK 3, BRAINARD TR

Tax Account No.: R097400510 **State ID No.:** R11E21AC 03900

Quarter Section: 2528

Neighborhood: Overlook, contact Claire Paris at 503-998-4878.

Business District: North Portland Business Assoc, contact Jim Schaller at 503-517-

9915.

District Coalition: North Portland Neighborhood Services, contact Mary Jaron Kelley at

503-823-4099.

Plan District: Albina Community

Zoning: R5 – Residential 5,000 square feet. **Case Type:** LDP – Land Division Partition

Procedure: Type I, an administrative decision with appeal to the Oregon Land Use

Board of Appeals (LUBA).

Proposal:

The applicant is proposing a two-lot partition on a property located on the corner of N. Humbolt Street and N. Denver Street. The site currently contains approximately 5,000 square feet of site area that will be divided into two 2,500 square foot lots for single family attached development. The existing tree and house will be removed. Stormwater will be managed on each site though the use of drywells.

This partition is reviewed through a Type I land use review because: (1) the site is in a residential zone; (2) fewer than four lots are proposed; (3) none of the lots, utilities, or services are proposed within a Potential Landslide Hazard or Flood Hazard Area, and; (4) no

other concurrent land use reviews (such as an Adjustment, Design Review, or Environmental Review) are requested or required (see 33.660.110).

For purposes of State Law, this land division is considered a partition. To partition land is to divide an area or tract of land into two or three parcels within a calendar year (See ORS 92.010).

Relevant Approval Criteria:

In order to be approved, this proposal must comply with the approval criteria of Title 33. The relevant approval criteria are found in 33.660 Reviews in Open Space and Residential Zones.

ANALYSIS

Site and Vicinity: The site is located in the Albina Community Plan District just west of Beach Elementary School. With the exception of the school, the surrounding properties are zoned R5 and are developed with single family houses typical of the residential development pattern for an R5 zone.

Zoning: The R5 designation is one of the City's single-dwelling zones which is intended to preserve land for housing and to promote housing opportunities for individual households. The zone implements the comprehensive plan policies and designations for single-dwelling housing.

The property is located in the Albina Community Plan District. The Albina Community plan district is intended to ensure that new higher density commercial and industrial developments do not overwhelm nearby residential areas. There are no required plan district standards that apply to this partition.

Land Use History: City records indicate there are no prior land use reviews for this site.

Agency and Neighborhood Review: A Notice of Proposal in your Neighborhood was mailed on January 6, 2009.

- **1. Agency Review:** Several Bureaus and agencies have responded to this proposal. Please see Exhibits E for details. The comments are addressed under the appropriate criteria for review of the proposal.
- **2. Neighborhood Review:** No written responses have been received from either the Neighborhood Association or notified property owners in response to the proposal.

APPROVAL CRITERIA

APPROVAL CRITERIA FOR LAND DIVISIONS IN OPEN SPACE AND RESIDENTIAL ZONES

33.660.120 The Preliminary Plan for a land division will be approved if the review body finds that the applicant has shown that all of the following approval criteria have been met.

The relevant criteria are found in Section **33.660.120 [A-L], Approval Criteria for Land Divisions in Open Space and Residential Zones**. Due to the specific location of this site, and the nature of the proposal, some of the criteria are not applicable. The following table summarizes the applicability of each criterion.

| Criterion | Code Chapter | Topic | Applicability Findings | |
|-----------|-----------------|-------|----------------------------------|--|
| A | 33.610 | Lots | Applicable - See findings below | |
| В | 33.630 | Trees | Applicable - See findings below. | |

| Criterion | Code Chapter | Topic | Applicability Findings |
|-----------|--------------------|----------------------------------------------------|-------------------------------------------------------------------------------------------------------|
| С | 33.631 | Flood Hazard Area | Not applicable - The site is not within the flood hazard area. |
| D | 33.632 | Potential Landslide Hazard Area | Not applicable - The site is not within the potential landslide hazard area. |
| Е | 33.633 | Phased Land Division or Staged Final Plat | Not applicable - A phased land division or staged final plat has not been proposed. |
| F | 33.634 | Recreation Area | Not applicable - This is not required where the proposed density is less than 40 units. |
| G | 33.635 .100 | Clearing and Grading | Applicable - See findings below. |
| G | 33.635 .200 | Land Suitability | Applicable - See findings below. |
| Н | 33.636 | Tracts and Easements | Applicable - See findings below. |
| I | 33.639 | Solar Access | Not applicable - The proposed development is for something other than single-dwelling detached homes. |
| J | 33.640 | Streams, Springs, and Seeps | Not applicable - No streams, springs, or seeps are evident on the site. |
| K | 33.641 | Transportation Impacts | Applicable - See findings below |
| L | 33.651 - 33.654 | Services and Utilities | Applicable - See findings below |

Applicable Approval Criteria are:

A. Lots. The standards and approval criteria of Chapters 33.605 through 33.612 must be met.

Findings: Chapter 33.610 contains the density and lot standards applicable in the RF through R5 zones. These density and lot dimension standards ensure that lots are consistent with the desired character of each zone while allowing lots to vary in size and shape provided the planned intensity of each zone is respected.

Density Standards

Density standards match housing density with the availability of services and with the carrying capacity of the land in order to promote efficient use of land, and maximize the benefits to the public from investment in infrastructure and services. These standards promote development opportunities for housing and promote urban densities in less developed areas. Maximum densities ensure that the number of lots created does not exceed the intensity planned for the area, given the base zone, overlay zone, and plan district regulations. Minimum densities ensure that enough dwelling units can be developed to accommodate the projected need for housing.

The method used to calculate density depends on whether a street is created as part of the land division, and whether the site is subject to certain environmental constraints.

In this case, a street is not proposed or required, and the site is <u>not</u> within the environmental zone, potential landslide hazard area, or flood hazard area. Therefore, the maximum and minimum density for this site is as follows:

Minimum = $(5,000 \text{ square feet * }.80) \div 5,000 \text{ square feet = }.8 \text{ (which rounds up to a minimum of 1 lot, per 33.930.020.A)}$

Maximum = 5,000 square feet ÷ 5,000 square feet = 1 (which rounds down to a maximum of 1 lot, per 33.930.020.B)

The applicant is proposing 2 lots, which exceeds the maximum density normally allowed for the site. However, Parcels 1 and 2 are proposed for attached houses under the provision in 33.110.240.E, which allows one extra unit in conjunction with attached houses on corner lots. Therefore, an additional lot is allowed provided Parcels 1 and 2 are developed with attached houses. With a condition of approval limiting the development on Parcels 1 and 2 to attached houses, the density standards are met.

The applicant is proposing 2 lots. The density standards are therefore met.

Lot Dimensions

The lot dimension standards ensure that: (1) each lot has enough room for a reasonably-sized house and garage; (2) lots are of a size and shape that development on each lot can meet the development standards of the Zoning Code; (3) lots are not too large relative to the planned density; (4) each lot has room for at least a small, private outdoor area; (5) lots are compatible with existing lots; (6) lots are wide enough to allow development to orient toward the street; (7) lots don't narrow to an unbuildable width close to the street; (8) each lot has adequate access from the street; (9) each lot has access for utilities and services; and (10) lots are not landlocked.

The dimensions of the proposed lots as compared to the required lot dimension standards is shown in the following table (this information is found in Table 610-2 of the Zoning Code):

| | R5 Zone Requirement | Proposed Lot 1 | Proposed Lot 2 |
|------------------------|------------------------|-------------------|-------------------|
| Minimum Lot Area | 3,000 sq. ft. | 2,500 | 2,500 |
| Maximum Lot Area | 8,500 sq. ft. | | |
| Minimum Lot Width* | 36 ft. | 50 | 50 |
| Minimum Lot Depth | 50 ft. | 50 | 50 |
| Minimum Front Lot Line | 30 ft. | 50 | 50 |

^{*} Width is measured at the minimum front building setback line

Attached Houses on Corner Lots

Parcels 1 and 2 are smaller than would normally be allowed in the R5 zone. As described above, these lots are being created through a provision that allows attached houses on corner lots. To use this provision, the original corner lot, before division must meet the minimum lot size standard of the R5 zone. Taken together (before the division), Parcels 1 and 2 combined are 5,000 square feet in area, which exceeds the minimum requirement of 3,000 square feet in the R5 zone. Therefore, the corner lot may be divided to create Parcels 1 and 2 as proposed.

B. Trees. The standards and approval criteria of Chapter 33.630, Tree Preservation, must be met.

Findings: The regulations of Chapter 33.630 preserve trees and mitigate for the loss of trees. Certain trees are exempt from the requirements of this chapter.

The applicant has submitted an arborist report that inventories the trees within the land division site, evaluates their condition and specifies root protection zones (Exhibit A-2). The inventory identifies the following tree on the site:

| Tree # | Species | Diameter | Significant? | Exempt? | To be | RPZ (Root |
|--------|---------|----------|------------------|------------------|-----------|------------------|
| | | (inches) | (On Table 630-1) | (per 33.630.030) | retained? | Protection Zone) |
| 1 | Tulip | 41 | Yes | No | No | N/A |

The total non-exempt tree diameter on the site is 41 inches. The applicant proposes to remove this tree due to its location and the small size of the site.

The proposal does not meet any of the tree preservation options in 66.630.100. The applicant proposes instead to use the mitigation options of 33.630.300:

33.630.300 Mitigation Option

As an alternative to meeting Section 33.630.100, approval of a mitigation plan may be requested. The review body will approve the mitigation plan where the applicant has shown that the applicant has met criteria A. and B. and one of the criteria in C., below:

- A. As many trees as possible are preserved; and
- B. The applicant has submitted a mitigation plan that adequately mitigates for the loss of trees, and shows how the mitigation plan equally or better meets the purpose of this chapter. Mitigation can include tree planting, preservation of groups of smaller trees, eco-roof, porous paving, or pervious surface permanently preserved in a tract.
- C. It is not possible under any reasonable scenario to meet Section 33.630.100 and meet one of the following:
 - 1. Minimum density;
 - 2. All service requirements of Chapters 33.651 through 33.654, including connectivity;
 - 3. Implementation of an adopted street plan;
 - 4. On sites 15,000 square feet or less in area, a practicable arrangement of lots, tracts, and streets within the site that would allow for the division of the site with enough room for a reasonable building site on each lot;
 - 5. In E and I zones, provide a practicable arrangement of lots, tracts, and streets within the site that would allow for the division of the site with enough room for a reasonable building site on each lot, considering the uses and development allowed in the zone; or
 - 6. Preserve the trees within the environmental zones on site while providing a practicable arrangement of building sites and disturbance area.

The site is less than 15,000 square feet in area. The applicant wishes to divide the site for attached housing, which is an allowed housing type in the R5 zone. The location of the existing tree would prevent a land division that would result in a practicable arrangement of lots that could each contain a reasonable building area and still be able to meet the development standards of the R5 zone. Criterion C.4 above is met.

The existing tree is on the northern half of Parcel 2. Due to its large size there is not adequate room to preserve the tree and develop the new Parcels with attached housing. Therefore, the applicant has meet Criteria A, because as many trees as possible will be preserved.

<u>Mitigation Plan:</u> The applicant has submitted a tree mitigation plan that mitigates for 14" of tree diameter. The applicant has proposed to plant 5 - 4" Bigleaf maple trees along the eastern property line of parcels 1 and 2.

The mitigation plan provides for equal caliper inches as would be required by Option 1 of the Tree Preservation Chapter. Option 1 would require that 35% or 14.35 inches of the existing tree diameter on site be preserved. The proposed 20" of tree diameter to be planted exceeds the required 14" of mitigation planting requirement.

<u>Response</u>: As mentioned above, the applicant is proposing to plant 5 trees along the eastern edge of Parcels 1 and 2. However, a 10' wide sanitary sewer easement is proposed along the northeast portion of Parcel 1, the same location that 3 trees are proposed for planting. The proposed trees and sewer lateral are not compatible uses, and may lead to problems for both

the trees as well as sewer line. Tree like shrubs are a more compatible plant to be placed in the easement area instead of the proposed trees. As an alternative to planting 3-4" maples on Parcel 1, the applicant will be required to plant three arborescent shrubs and $1-2\frac{1}{2}$ " Big Leaf Maple on Parcel 1. Three 4" Big Leaf Maple trees shall be required on Parcel 2. The $14\frac{1}{2}$ " and 3 arborescent shrubs adequately mitigates for the loss of the existing tree.

The new trees and shrubs that will be planted as part of the mitigation plan will help absorb air pollutants and contamination, provide buffering from noise and wind, and provide visual screening from the adjacent properties. The dispersion of the mitigation trees allows more areas of the site to reap the benefits of trees that are described in the purpose statement for the Tree Preservation Chapter. In addition, the trees will grow over time to provide additional benefits.

Section 33.248.020.H, known as the T1 tree planting standard, requires trees to be planted on new lots as part of the approval of future building permits. In this case the T1 tree standard requires the planting of at least 3 inches of tree caliper for parcels less than 3,000 square feet of site area, which would result in 3 inches of new tree diameter for each of the proposed lots. Because of the small size of the parcels it is not practical for additional trees beyond the T1 standard to be planted without jeopardizing the overall health of all of the trees on the site. Therefore, the mitigation trees may be counted toward meeting the T1 requirement on the new lots.

Criteria B is met with a condition of approval requiring 3 trees to be planted on Parcel 2 and 1 tree and three arborescent shrubs to be planted on Parcel 1 prior to final building permit approval for new houses on these lots.

G. Clearing, Grading and Land Suitability. The approval criteria of Chapter 33.635, Clearing, Grading and Land Suitability must be met.

The approval criteria of Chapter 33.635 are found in two groups – clearing and grading, and land suitability.

33.635.100 - Clearing and Grading

- A. Existing contours and drainage patterns of the site must be left intact wherever practicable. Where alteration to existing drainage patterns is proposed, it must not adversely impact adjacent properties by significantly increasing volume of runoff or erosion;
- B. Clearing and grading should be sufficient for construction of development shown on the Preliminary Clearing and Grading Plan;
- C. Clearing and grading should be limited to areas of the site that are reasonably necessary for construction of development shown on the Preliminary Clearing and Grading Plan;
- D. Topsoil must be preserved on site to the extent practicable for use on the site after grading is complete; and
- E. Soil stockpiles must be kept on the site and located in areas designated for clearing and grading as much as is practicable.

Findings: The regulations of Chapter 33.635 ensure that the proposed clearing and grading is reasonable given the infrastructure needs, site conditions, tree preservation requirements, and limit the impacts of erosion and sedimentation to help protect water quality and aquatic habitat.

In this case the site is primarily flat, and is not located within the Potential Landslide Hazard Area. Therefore, no significant clearing or grading will be required on the site to make the new lots developable. In addition, there are no trees required to be preserved in the areas where new development on the site is anticipated. This criteria is met.

Where geologic conditions or historic uses of the site indicate a hazard may exist, the applicant must show that the proposed land division will result in lots that are suitable for development. The applicant may be required to make specific improvements in order to make the lots suitable for their intended uses and the provision of services and utilities.

The site is currently in residential use, and there is no record of any other use in the past. The applicant has proposed to remove the existing house and garage and redevelop the site. In order to ensure that the new lots are suitable for development, a permit must be obtained and finalized for demolition of all structures on the site and sewer capping prior to final plat approval. With this condition, the new lots can be considered suitable for development, and this criterion is met.

H. Tracts and easements. The standards of Chapter 33.636, Tracts and Easements must be met;

33.636.100 Requirements for Tracts and Easements

- A. Ownership of tracts. Tracts must be owned as follows unless otherwise specified in this Title or the land use decision:
 - 1. The owners of property served by the tract, or by any other individual or group of people. When the tract is owned by more than one person it must be held in common with an undivided interest;
 - 2. The Homeowners' Association for the area served by the tract;
 - 3. A public or private non-profit organization; or
 - 4. The City or other jurisdiction.

Findings: No tracts are proposed or required for this land division, so criterion A does not apply.

B. Maintenance agreement. The applicant must record with the County Recorder a maintenance agreement that commits the owners or owners' designee to maintain all elements of the tract or easement; however, facilities within the tract or easement that will be maintained by a specified City agency may be recorded in a separate maintenance agreement. The maintenance agreement must be approved by BDS and the City Attorney in advance of Final Plat approval and must be submitted to the County Recorder to be recorded with the Final Plat. For a Planned Development not done in conjunction with a land division, the maintenance agreement must be submitted to the County Recorder to be recorded prior to issuance of the first building permit related to the development.

Findings: The following easements are proposed and/or required for this land division:

• A Private Sanitary Sewer Easement is required across the relevant portions of Parcel 1, for a sanitary sewer lateral connection that will serve Parcel 2.

As stated in Section 33.636.100 of the Zoning Code, a maintenance agreement(s) will be required describing maintenance responsibilities for the easement described above and facilities within the area. This criterion can be met with the condition that a maintenance agreement is prepared and recorded with the final plat. In addition, the plat must reference the recorded maintenance agreement with a recording block for the agreement, substantially similar to the following example:

"A Declaration of Maintenance agreement for the private sanitary sewer easement has been recorded as document no. ______, Multnomah County Deed Records."

With the conditions of approval discussed above, this criterion is met.

K. Transportation impacts. The approval criteria of Chapter 33.641, Transportation Impacts, must be met; and,

The relevant approval criteria of Chapter 33.641 are found in the two paragraphs below.

33.641.020. The transportation system must be capable of safely supporting the proposed development in addition to the existing uses in the area. Evaluation factors include: street capacity and level-of-service; vehicle access and loading; onstreet parking impacts; the availability of transit service and facilities and connections to transit; impacts on the immediate and adjacent neighborhoods; and safety for all modes.

33.641.030. The applicant may meet the criterion in Section 33.641.020, above, by including mitigation measures as part of the land division proposal. Mitigation measures must be acceptable to the City Engineer and may include providing transportation demand management measures, an access management plan, constructing streets or bicycle, pedestrian, or transit facilities on or off the site or other capital improvement projects such as traffic calming devices.

Findings: The regulations of Chapter 33.641 allow the traffic impacts caused by dividing and then developing land to be identified, evaluated, and mitigated for if necessary. Small land divisions involving only a few dwelling units may not require a formal transportation impact study, while it might be required for larger projects (Title 17 includes technical standards describing when a more formal study is required).

The site has approximately 100 feet of frontage on N. Denver Avenue and 50 feet of frontage on N Humbolt Street. N Humbolt Street is classified as a local service street for all modes in the Transportation Element of the Comprehensive Plan. N. Denver Street is designated as a local service street and City Walkway. Tri-Met provides transit service approximately 900 feet from the site on N Greeley Avenue via bus #72. Parking is currently allowed on N Humbolt Street and N Denver Street on both sides. There is one driveway entering the site that provides access to off-street parking for the existing house.

Both N Humboldt Street and N Denver Street are fully improved with a paved roadway, curbs, planting strips, and sidewalks. In reviewing this land division, Portland Transportation relies on accepted civil and traffic engineering standards and specifications to determine if existing street improvements for motor vehicles, pedestrians and bicyclists can safely and efficiently serve the proposed new development. Portland Transportation has not identified or been made aware of any factors related to this proposal that lead to a conclusion other than that one additional dwelling can be safely served by this existing street without having any significant impact on the level of service provided.

This criterion is met.

L. Services and utilities. The regulations and criteria of Chapters 33.651 through 33.654, which address services and utilities, must be met.

Findings: Chapters 33.651 through 33.654 address water service standards, sanitary sewer disposal standards, stormwater management, utilities and rights of way.

- The water standards of 33.651 have been verified. An existing 8 -inch water main is available in N Denver Avenue. Water is available to serve the proposed development from the water main in N Denver Avenue. Parcel 2 has an existing water service from that main. See Exhibit E-3 for more details.
- The sanitary sewer standards of 33.652 have been verified. There is an existing 12" public combination sanitary sewer located in N Humbolt Street that can serve the sanitary needs of the proposed lots. A private sanitary easement will be required across

Parcel 1, for the benefit of Parcel 2 to provide sanitary services. See Exhibit E-1 for more details.

• The technical standards of Chapter 33.653 related to stormwater management have been verified. The findings below for the Stormwater Management Approval Criteria of 33.653.020 incorporate a discussion of how the technical standards have been satisfied by the applicant's stormwater proposal.

33.653.020 Stormwater Management Approval Criteria

- A. If a stormwater tract is proposed or required, an adequate amount of land and an appropriate location must be designated on the Preliminary Plan; and
- B. The application must show that a stormwater management system can be designed that will provide adequate capacity for the expected amount of stormwater.

Findings: No stormwater tract is proposed or required. Therefore, criterion A is not applicable.

The City of Portland requires that stormwater from development be cleaned and disposed of in a manner that meets the requirements of the City's <u>Stormwater Management Manual</u>. In order to meet this approval criterion, land division proposals must demonstrate an approved method of cleaning (water quality treatment), detention (delayed release), and an approved disposal point.

The <u>Stormwater Management Manual</u> contains a hierarchy of acceptable methods of stormwater treatment and disposal. The hierarchy requires that applicants first explore the use of methods that have a lower potential impact on groundwater, such as on-site surface infiltration swales and infiltration planters. If these methods are not feasible on a site, applicants may move lower on the hierarchy, to methods that inject water deeper into the ground through mechanical devices such as drywells or sumps, or carry it off of the site into storm sewers, drainageways, or other approved disposal points.

In addition to determining appropriate treatment and disposal methods by working through the hierarchy in the <u>Stormwater Management Manual</u>, stormwater facilities must be sized, through engineering calculations, to accommodate the expected amounts of stormwater. In some cases, sizing a stormwater facility necessitates testing the infiltration rate of the soil at the site.

The applicant has proposed the following stormwater management methods (Exhibit C), and the Bureaus have responded as follows (Exhibits E-1 and E-5).

• **Parcels 1 and 2:** Stormwater from these parcels will be directed to individual drywells that will treat the water and slowly infiltrate it into the ground. Each of these lots has sufficient area for a stormwater facility that can be adequately sized and located to meet setback standards, and accommodate water from a reasonably-sized home. Site Development has indicated conceptual approval of the drywells.

With the conditions of approval described above, the stormwater management criteria are met. As shown by the findings above, the Services and Utilities criteria are met.

Right of Way Approval Criteria

Chapter 33.654 contains standards and approval criteria for rights of way. Due to the location of this site, and the type of street that is proposed, some of the criteria are not applicable. The following table summarizes the applicability of each criterion.

| Code Section | Topic | Applicability Findings |
|------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------|
| 33.654.110.B.1 | Through streets and pedestrian connections | Applicable - See findings below |
| 33.654.110.B.2 | Dead end streets | Not applicable - No dead end streets are proposed. |
| 33.654.110.B.3 | Pedestrian connections in the I zones | Not applicable - The site is not located within an I zone. |
| 33.654.110.B.4 | Alleys in all zones | Not applicable – No alleys are proposed or required. |
| 33.654.120.C.1 | Width of the street right-of- way | Not applicable – The proposal includes a common green/shared court/pedestrian connection instead of a traditional street. |
| 33.654.120.C.3.c | Turnarounds | Not applicable – No turnarounds are proposed or required. |
| 33.654.120.D | Common Greens | Not applicable – No common greens are proposed or required. |
| 33.654.120.E | Pedestrian Connections | Not applicable – There are no pedestrian connections proposed or required. |
| 33.654.120.F | Alleys | Not applicable – No alleys are proposed or required. |
| 33.654.120.G | Shared Courts | Not applicable – No shared courts are proposed or required. |
| 33.654.130.A | Utilities | Applicable - See findings below. |
| 33.654.130.B | Extension of existing public dead-end streets and pedestrian connections | Not applicable – There are no existing public dead-end street or pedestrian connections adjacent to the site. |
| 33.654.130.C | Future extension of proposed dead- end streets and pedestrian connections | Not applicable – No street extensions are required to serve abutting sites that are further dividable. |
| 33.654.130.D | Partial rights-of- way | Not applicable – No partial public streets are proposed or required. |

Applicable Approval Criteria are:

33.654.110.B.1 Approval criterion for through streets and pedestrian connections in OS, R, C, and E Zones. In OS, R, C, and E zones, through streets and pedestrian connections are required where appropriate and practicable, taking the following into consideration:

- a. Through streets should generally be provided no more than 530 feet apart, and pedestrian connections should generally be provided no more than 330 feet apart. Through street and pedestrian connections should generally be at least 200 feet apart;
- b. Where the street pattern in the area immediately surrounding the site meets the spacing of subparagraph a., above, the existing street pattern should be extended onto the site;
- c. Characteristics of the site, adjacent sites, and vicinity, such as: (1) Terrain; (2) Whether adjacent sites may be further divided; (3) The location of existing streets and pedestrian connections; (4) Whether narrow frontages will constrain creation of a through street or pedestrian connection; (5) Whether environmental overlay zones interrupt the expected path of a through street or pedestrian connection; and (6) Whether existing dwelling units on- or off-site obstruct the expected path of a through street or pedestrian connection.

Alternative locations or designs of rights-of-way should be considered that avoid existing dwelling units. However, provision of through streets or pedestrian connections should take precedence over protection of existing dwelling units where the surrounding transportation system will be significantly affected if a new through street or pedestrian connection is not created;

- d. Master street plans for the area identified in Goal 11B of the Comprehensive Plan:
- e. Pedestrian connections should take the most direct route practicable. Users should be able to see the ending of the connection from the entrance point, if possible.

Findings: The site is a corner lot located between N Humbolt Street and N Wygant Street which have a distance between them of approximately 200 feet. There are no other east/west through streets between these two streets. If the distance between these existing streets is evaluated against the optimum spacing requirement of 530 feet, one can conclude that there should not be an east-west or north/south through street provided in the vicinity of the site. A through street is not proposed or appropriate at this location.

In addition, the site is not within an area that has an adopted Master Street Plan, so criterion d. does not apply.

There are existing sidewalks along both N Humbolt and N Denver Street. No additional pedestrian connections are proposed or required.

For the reasons described above, this criterion is met.

Utility Location, Extension of Streets, Partial Rights of Way

33.654.130 Additional Approval Criteria for Rights-of-Way

A. Utilities. Utilities must be located within rights-of-way or utility easements that are adjacent to rights-of-way to the maximum extent practicable. Utility easements up to 15 feet in width may be required adjacent to rights-of-way.

Findings: Utilities are defined in the Zoning Code as telephone, cable, natural gas, electric, and telecommunication facilities. Any easements that may be needed for private utilities that cannot be accommodated within the existing right-of-way can be provided on the final plat. At this time no specific utility easements adjacent to the street tract right-of-way have been identified as being necessary. Therefore, this criterion is met.

DEVELOPMENT STANDARDS

General Information about Development Standards and Approval Criteria. The Zoning Code contains two types of regulations: Development standards and Approval criteria.

Approval criteria, such as those listed earlier in this report, are administered through a land use review process. Approval criteria are regulations where the decision-maker must exercise discretion to determine if the regulation is met. Public notice is provided and public comments received that address the approval criteria are addressed in the decision.

Development Standards: Development standards are clear and objective regulations (for example: building setbacks; number of required parking spaces; and maximum floor area). Compliance with development standards is reviewed as part of the administrative permitting process and are not considered to be discretionary reviews. Development standards that are not relevant to the land division review, have not been addressed in the review, but will have to be met at the time that each of the proposed lots is developed.

<u>Attached Houses on Corner Lots</u>-- special requirements apply to development on new lots created using the provisions of Section 33.110.240.E. The address and main entrance of each house must be oriented to a separate street frontage. Development on Parcel 1 must be oriented toward N. Humbolt Street and development on Parcel 2 must be oriented toward N. Denver Avenue.

OTHER TECHNICAL REQUIREMENTS

Technical decisions have been made as part of this review process. These decisions have been made based on other City Titles, adopted technical manuals, and the technical expertise of appropriate service agencies. These related technical decisions are not considered land use actions. If future technical decisions result in changes that bring the project out of conformance with this land use decision, a new land use review may be required. The following is a summary of technical service standards applicable to this preliminary partition proposal.

| Bureau | Code | Topic | Contact Information |
|----------------|-----------------|-------------------|-------------------------------------|
| | Authority | | |
| Water Works | Title 21 | Water | 503-823-7404 |
| | | availability | http://www.water.ci.portland.or.us/ |
| Environmental | Title 17; 2002 | Sewer | 503-823-7740 |
| Services | Stormwater | availability | http://www.bes.ci.portland.or.us/ |
| | Manual | Stormwater | |
| | | Management | |
| Fire Bureau | Title 31 | Emergency | 503-823-3700 |
| | Policy B-1 | Access | http://www.fire.ci.portland.or.us/ |
| Transportation | Title 17, | Design of public | 503-823-5185 |
| | Transportation | street | http://www.trans.ci.portland.or.us/ |
| | System Plan | | |
| Development | Titles 24 –27, | Building Code, | 503-823-7300 |
| Services | Admin Rules for | Erosion Control, | http://www.bds.ci.portland.or.us. |
| | Private Rights | Flood plain, Site | |
| | of Way | Development & | |
| | | Private Streets | |

As authorized in Section 33.800.070 of the Zoning Code conditions of approval related to these technical standards have been included in the Administrative Decision on this proposal.

CONCLUSIONS

- The applicant has proposed a 2 lot partition, as shown on the attached preliminary plan (Exhibit C-1). As discussed in this report, the relevant standards and approval criteria have been met, or can be met with conditions. The primary issues identified with this proposal are:
 - Planting the required trees and shrubs at the time of development
 - Meeting Corner lot standards
 - Creating the required 10' sanitary sewer easement.

With conditions of approval that address these requirements this proposal can be approved.

ADMINISTRATIVE DECISION

Approval of a Preliminary Plan for a 2-lot partition that will result in two single family parcels for attached development as illustrated with Exhibit C-1, subject to the following conditions:

A. The final plat must show the following:

- 1. A private sanitary sewer easement, for the benefit of Parcel 2, shall be shown and labeled over the relevant portions of Parcel 1.
- 2. A recording block for the legal maintenance agreement, as required by Condition B2 below. The recording block(s) shall, at a minimum, include language substantially similar to the following example: "A Declaration of Maintenance Agreement for a private sewer easement has been recorded as document no. ______, Multnomah County Deed Records."

B. The following must occur prior to Final Plat approval:

Existing Development

1. A finalized permit must be obtained for demolition of the existing residence on the site and capping the existing sanitary sewer connection. (if the demo includes a primary residential structure, add:) Note that Title 24 requires a 35-day demolition delay period for most residential structures.

Required Legal Documents

- 2. A Maintenance Agreement shall be executed for the Private Sewer Easement area described in Condition A2 above. The agreement shall include provisions assigning maintenance responsibilities for the easement area and any shared facilities within that area, consistent with the purpose of the easement, and all applicable City Code standards. The agreement must be reviewed by the City Attorney and the Bureau of Development Services, and approved as to form, prior to final plat approval.
- C. The following conditions are applicable to site preparation and the development of individual lots:
- 1. Development on Parcels 1 and 2 shall be in approximate conformance with the Tree Planting Plan (Exhibit C-2). Specifically one 2^{1/2}" Big Leaf Maple Tree and three arborescent shrubs shall be planted on Parcel 1. Three 4" Big Leaf Maple trees must be planted on Parcel 2 prior to building permit approval. Trees other than Big Leaf Maples can be substituted as long as they are approved by an arborist and are at least 4" in size.
- 2. Parcels 1 and 2 may only be developed with attached houses meeting the development standards of Section 33.110.240.E.

Decision rendered by: ______ on February 27, 2009

By authority of the Director of the Bureau of Development Services

Decision mailed (within 5 days of dec.) March 3, 2009

Staff Planner: Mieke Stekelenburg

About this Decision. This land use decision is **not a permit** for development. A Final Plat must be completed and recorded before the proposed lots can be sold or developed. Permits may be required prior to any work. Contact the Development Services Center at 503-823-7310 for information about permits.

Procedural Information. The application for this land use review was submitted on November 26, 2008, and was determined to be complete on December 31, 2008.

Zoning Code Section 33.700.080 states that Land Use Review applications are reviewed under the regulations in effect at the time the application was submitted, provided that the

application is complete at the time of submittal, or complete within 180 days. Therefore this application was reviewed against the Zoning Code in effect on November 26, 2008.

ORS 227.178 states the City must issue a final decision on Land Use Review applications within 120-days of the application being deemed complete. The 120-day review period may be waived or extended at the request of the applicant. In this case, the applicant did not waive or extend the 120-day review period.

Some of the information contained in this report was provided by the applicant.

As required by Section 33.800.060 of the Portland Zoning Code, the burden of proof is on the applicant to show that the approval criteria are met. The Bureau of Development Services has independently reviewed the information submitted by the applicant and has included this information only where the Bureau of Development Services has determined the information satisfactorily demonstrates compliance with the applicable approval criteria. This report is the decision of the Bureau of Development Services with input from other City and public agencies.

Conditions of Approval. If approved, this project may be subject to a number of specific conditions, listed above. Compliance with the applicable conditions of approval must be documented in all related permit applications. Plans and drawings submitted during the permitting process must illustrate how applicable conditions of approval are met. Any project elements that are specifically required by conditions of approval must be shown on the plans, and labeled as such.

These conditions of approval run with the land, unless modified by future land use reviews. As used in the conditions, the term "applicant" includes the applicant for this land use review, any person undertaking development pursuant to this land use review, the proprietor of the use or development approved by this land use review, and the current owner and future owners of the property subject to this land use review.

This decision, and any conditions associated with it, is final. It may be appealed to the Oregon Land Use Board of Appeals (LUBA), within 21 days of the date the decision is mailed, as specified in the Oregon Revised Statute (ORS) 197.830. Among other things, ORS 197.830 requires that a petitioner at LUBA must have submitted written testimony during the comment period for this land use review. You may call LUBA at 1-503-373-1265 for further information on filing an appeal.

The file and all evidence on this case is available for your review by appointment. Please contact the receptionist at 503-823-7967 to schedule an appointment. Copies of all information in the file can be obtained for a fee equal to the cost for such services. You may also find additional information about the City of Portland and City Bureaus, as well as a digital copy of the Portland Zoning Code, by visiting the City's homepage on the Internet at www.portlandonline.com.

Recording the land division. The final land division plat must be submitted to the City within three years of the date of the City's final approval of the preliminary plan. This final plat must be recorded with the County Recorder and Assessors Office after it is signed by the Planning Director or delegate, the City Engineer, and the City Land Use Hearings Officer, and approved by the County Surveyor. The approved preliminary plan will expire unless a final plat is submitted within three years of the date of the City's approval of the preliminary plan.


EXHIBITS

NOT ATTACHED UNLESS INDICATED

- A. Applicant's Statement
 - 1. Narrative
 - 2. Arborist Report
 - 3. Stormwater Report
- B. Zoning Map (attached)

- C. Plans/Drawings:
 - 1. Site Plan (attached)
 - 2. Tree Planting Plan (attached)
- D. Notification information:
 - 1. Mailing list
 - 2. Mailed notice
- E. Agency Responses:
 - 1. Bureau of Environmental Services
 - 2. Bureau of Transportation Engineering and Development Review
 - 3. Water Bureau
 - 4. Fire Bureau
 - 5. Site Development Review Section of BDS
 - 6. Bureau of Parks, Forestry Division
 - 7. Life Safety Section of Bureau of Development Services
- F. Correspondence: None Submitted
- G. Other:
 - 1. Original LU Application
 - 2. Site History Research
 - 3. Incomplete Letter.

The Bureau of Development Services is committed to providing equal access to information and hearings. If you need special accommodations, please call 503-823-0625 (TTY 503-823-6868).



ZONING




File No. 2528 1/4 Section 1 inch = 200 feet Scale. 1N1E21AC 3900 State_Id В (Feb 27,2009)

Exhibit.



This site lies within the: ALBINA COMMUNITY PLAN DISTRICT



Tue Planting Plan CONTINUE GRAVITY MAN - VERTY & OF N HUMBOLDT STREET, A 64'-0' ROW PRESS,RIED HAN . VERPY 212" Bigley Maple 10 wide sever edounch 0 0 * CONCRETE OF N DENVER AVENUE, A 60'-0" ROU LINE OF 15" FRONT SETEACK (MIN) 0 0 LNE OF 5' BOE BETBACK (MN) LINE OF IS GARAGE SETBACK (MIN) Ar balescend Shrub 25657 OME NOOF LINE OF 5' REAR SETBACK (MN) (1) × 10 LINE OF 5" SIDE SETBACK (MINU ENE OF B'GARAGE 器 NO DO DO E LNZ OF 10' FRONT -4" Big Leap Maple

> CASE NO. 08-180500 EXEMPLE C-2