



City of Portland, Oregon
Bureau of Development Services
Land Use Services
 FROM CONCEPT TO CONSTRUCTION

Chloe Eudaly, Commissioner
 Rebecca Esau, Director
 Phone: (503) 823-7300
 Fax: (503) 823-5630
 TTY: (503) 823-6868
www.portlandoregon.gov/bds

Date: March 8, 2018
To: Interested Person
From: Emily Hays, Land Use Services
 503-823-5676 / Emily.Hays@portlandoregon.gov

NOTICE OF A TYPE Ix DECISION ON A PROPOSAL IN YOUR NEIGHBORHOOD

The Bureau of Development Services has approved a proposal in your neighborhood. The mailed copy of this document is only a summary of the decision. The reasons for the decision are included in the version located on the BDS website <http://www.portlandonline.com/bds/index.cfm?c=46429>. Click on the District Coalition then scroll to the relevant Neighborhood, and case number. If you disagree with the decision, you can appeal. Information on how to do so is included at the end of this decision.

CASE FILE NUMBER: LU 18-111036 HR - *BROADWAY BUILDING BLADE SIGN*

GENERAL INFORMATION

Applicant: Stephen Blackstone | IA Interior Architects, PC
 1120 NW Couch Street #450 | Portland, OR 97209
s.blackstone@interiorarchitects.com

Owner: Natsumi Shakhman
 Goodman Generation C/O Downtown Development Group
 920 SW 6th Avenue #223 | Portland, OR 97204

Representative: Terrence Casey | JLL - Capital One Account
 906 Catalina Avenue | Santa Ana, CA 92706

Site Address: **715 SW Morrison Street**

Legal Description: BLOCK 212 LOT 4, PORTLAND
Tax Account No.: R667722820, R667722820
State ID No.: 1N1E34CC 08600, 1N1E34CC 08600
Quarter Section: 3029

Neighborhood: Portland Downtown, contact Rani Boyle at 503-725-9979.
Business District: Downtown Retail Council, contact Sandra McDonough at 503-552-6762.
District Coalition: Neighbors West/Northwest, contact Mark Sieber at 503-823-4212.

Plan District: Central City - Downtown
Other Designations: Historic Landmark – Listed on the National Register of Historic Places
Zoning: **CXd** – Central Commercial with Design & Historic Resource Review Overlays
Case Type: **HR** – Historic Resource Review
Procedure: **Type Ix** - an administrative decision with appeal to the Oregon Land Use Board of Appeals (LUBA).

Proposal:
 The applicant is seeking Historic Resource Review for a new 30 SF blade sign on a Historic Landmark in the Downtown Subdistrict of the Central City Plan District. The corner projecting blade sign is vertically oriented and has an approximately 3' x 10' sign face with

push-thru acrylic elements. Four (4) red LED stripes run vertically along the 1' cabinet return. The existing brick will be removed and reinstalled to accommodate two (2) metal bracket mounts.

Historic Resource Review is required for new non-exempt signs on a Historic Landmark.

Relevant Approval Criteria:

In order to be approved, this proposal must comply with the approval criteria of Title 33, Portland Zoning Code. The relevant approval criteria are:

- Central City Fundamental Design Guidelines
- 33.846.060G – Other Approval Criteria

ANALYSIS

Site and Vicinity: The historic Broadway Building, also known as the Pioneer Park Building, is located in the Central City Plan District at the northwest corner of SW Broadway and SW Morrison. It is an 11-story structure located diagonally across from Pioneer Courthouse Square and contributes to its sense of urban enclosure. Five of the other buildings surrounding the square are also designated historic structures, creating an ensemble that largely defines the character of the open space.

Designed by Portland architect E.B. MacNaughton in the Commercial style, the Pioneer Park Building was completed and opened for use in 1913. It is a Commercial Style composition with influences from the Chicago School, a highly popular architectural movement at the time. The building has a primary façade that fronts SW Morrison and a secondary façade fronting SW Broadway. The exterior is primarily clad in white pressed brick, with terra cotta and painted sheet metal trim elements. There is a shallow light well on the north party wall.

The Morrison Street façade is divided into six bays, each approximately 18 feet wide. The SW Broadway façade is three bays wide. The ground and second floors have been repeatedly altered over time, and while their current configuration is reasonably compatible with the historic character of the building, virtually no intact historic fabric remains there.

SW Morrison St is designated a Regional Transitway and Major Transit Priority Street. SW Broadway is designated a District Collector Street and a City Bikeway and Walkway. The site is within the Downtown Pedestrian District.

Zoning: The Central Commercial (CX) zone is intended to provide for commercial development within Portland's most urban and intense areas. A broad range of uses is allowed to reflect Portland's role as a commercial, cultural and governmental center. Development is intended to be very intense with high building coverage, large buildings, and buildings placed close together. Development is intended to be pedestrian-oriented with a strong emphasis on a safe and attractive streetscape.

The "d" overlay promotes the conservation and enhancement of areas of the City with special historic, architectural or cultural value. New development and exterior modifications to existing development are subject to design review. This is achieved through the creation of design districts and applying the Design Overlay Zone as part of community planning projects, development of design guidelines for each district, and by requiring design review. In addition, design review ensures that certain types of infill development will be compatible with the neighborhood and enhance the area.

The Historic Resource Protection overlay is comprised of Historic and Conservation Districts, as well as Historic and Conservation Landmarks and protects certain historic resources in the region and preserves significant parts of the region's heritage. The regulations implement Portland's Comprehensive Plan policies that address historic preservation. These policies recognize the role historic resources have in promoting the education and enjoyment of those living in and visiting the region. The regulations foster pride among the region's citizens in their city and its heritage. Historic preservation beautifies the city, promotes the city's economic health, and helps to preserve and enhance the value of historic properties.

Land Use History: City records indicate that prior land use reviews include the following:

- DZ 34-84: Design Review approval for a storefront remodel.
- DZ 97-86: Design Review approval for the renovation of the lobby and exterior canopy.

- DZ 72-90: Design Review approval for a remodel/restoration.
- LUR 96-00137 DZ: Design Review approval for the renovation of the first two floors of the Pioneer Park Building.
- LU 03-119357 HDZ: Historic Design Review approval of exterior light fixtures.
- LU 06-117546 HDZ: Historic Design Review approval of new entry doors, windows, and signage.
- LU 09-104260 HDZ: Historic Design Review approval of six panel antennae, six DAP units, four microwave dishes, one GPS unit, and one support cabinet onto the existing rooftop penthouse of the Pioneer Park Building.
- LU 09-126107 HDZ: Approval of a new metal and glass building entrance.
- LU 11-109571 HDZ: Historic Design Review approval to install one surface-mounted, internally illuminated sign and one non-illuminated blade sign.
- LU 17-198394 HR: Approval of halo illuminated signs above each of the doors, new doors, new tenant plaque sign at the corner column, and re-glazing the storefronts with clear glass.

Agency Review: A Notice of Proposal in your Neighborhood was mailed on **February 2, 2018**. The following Bureaus have responded with no issues or concerns about the proposal:

- Fire Bureau
- Site Development Section of BDS
- Life Safety Review Section of BDS, *See Exhibit E-1*

Neighborhood Review: A Notice of Proposal in Your Neighborhood was mailed on **February 2, 2018**. No written responses have been received from either the Neighborhood Association or notified property owners in response to the proposal.

ZONING CODE APPROVAL CRITERIA

Chapter 33.846, Historic Reviews

Purpose of Historic Resource Review

Historic Resource Review ensures the conservation and enhancement of the special characteristics of historic resources.

Historic Resource Review Approval Criteria

Requests for Historic Resource Review will be approved if the review body finds the applicant has shown that all of the approval criteria have been met.

Findings: The site is a designated Historic Landmark. Therefore, the proposal requires Historic Resource Review approval. The relevant approval criteria are listed in 33.846.060 G. 1.-10. In addition, because the site is located within the Central City, the relevant approval criteria are the Central City Fundamental Design Guidelines.

G. Other Approval Criteria:

- 1. Historic character.** The historic character of the property will be retained and preserved. Removal of historic materials or alteration of features and spaces that contribute to the property's historic significance will be avoided.
- 2. Record of its time.** The historic resource will remain a physical record of its time, place, and use. Changes that create a false sense of historic development, such as adding conjectural features or architectural elements from other buildings will be avoided.
- 3. Historic changes.** Most properties change over time. Those changes that have acquired historic significance will be preserved.
- 4. Historic features.** Generally, deteriorated historic features will be repaired rather than replaced. Where the severity of deterioration requires replacement, the new feature will match the old in design, color, texture, and other visual qualities and, where practical, in materials. Replacement of missing features must be substantiated by documentary, physical, or pictorial evidence.
- 5. Historic materials.** Historic materials will be protected. Chemical or physical treatments, such as sandblasting, that cause damage to historic materials will not be used.

Findings: The addition of the proposed sign will not alter the distinguishing features of the Landmark building. The sign will be located on an existing corner column and aligned below the second level window openings. The two corner mount brackets for the sign will be installed through the existing structural column, with existing brick removed and replaced after installation. The sign bracket will follow the contour of the corner to avoid removal or damage of additional exterior materials. The scale and proportion of the proposed sign will not compete with or impact the visual integrity of the structure.

A historic photo, dated January 1914, provided by the applicant shows a large blade sign in this location. As a commercial building, this type of signage maintains a record of the Landmark's time, place, and use. No chemical or physical treatments that would damage historic materials have been proposed. *With condition of approval E that sign brackets be installed behind the existing brick and fully concealed, these guidelines have been met.*

- 6. Archaeological resources.** Significant archaeological resources affected by a proposal will be protected and preserved to the extent practical. When such resources are disturbed, mitigation measures will be undertaken.

Findings: No significant archaeological resources are affected by this proposal. *Therefore, this criterion does not apply.*

- 7. Differentiate new from old.** New additions, exterior alterations, or related new construction will not destroy historic materials that characterize a property. New work will be differentiated from the old.
- 8. Architectural compatibility.** New additions, exterior alterations, or related new construction will be compatible with the resource's massing, size, scale, and architectural features. When retrofitting buildings or sites to improve accessibility for persons with disabilities, design solutions will not compromise the architectural integrity of the historic resource.
- 9. Preserve the form and integrity of historic resources.** New additions and adjacent or related new construction will be undertaken in such a manner that if removed in the future, the essential form and integrity of the historic resource and its environment would be unimpaired.
- 10. Hierarchy of compatibility.** Exterior alterations and additions will be designed to be compatible primarily with the original resource, secondarily with adjacent properties, and finally, if located within a Historic or Conservation District, with the rest of the district. Where practical, compatibility will be pursued on all three levels.

Findings: The new sign will be differentiated through contemporary materials; the aluminum cabinet features push-thru acrylic copy and is trimmed by four LED stripes. The proposed sign will be illuminated; the junction box will be located on the interior of the building, connected by a conduit housed in the sign's attachment arm to discreetly connect with interior electrical through the building wall. The unobtrusive placement of the sign ensures that were it to be removed, the essential form, architectural features and overall character of the resource would be unaltered.

The overall design and articulation of the sign help to activate and identify the storefront and use of the tenant space without detracting from the building. In general, the sign is appropriately scaled, placed and of a form and character consistent with its prominent location on a Landmark structure in a commercial area of the Central City. *With condition of approval D that all electrical shall be fully concealed, these guidelines have been met.*

Central City Fundamental Design Guidelines

These guidelines provide the constitutional framework for all design review areas in the Central City.

The Central City Fundamental Design Guidelines and the River District Design Guidelines focus on four general categories. **(A) Portland Personality**, addresses design issues and elements that reinforce and enhance Portland's character. **(B) Pedestrian Emphasis**, addresses design issues and elements that contribute to a successful pedestrian environment. **(C) Project Design**, addresses specific building characteristics and their

relationships to the public environment. **(D) Special Areas**, provides design guidelines for the four special areas of the Central City.

Central City Plan Design Goals

This set of goals are those developed to guide development throughout the Central City. They apply within the River District as well as to the other seven Central City policy areas. The nine goals for design review within the Central City are as follows:

1. Encourage urban design excellence in the Central City;
2. Integrate urban design and preservation of our heritage into the development process;
3. Enhance the character of the Central City's districts;
4. Promote the development of diversity and areas of special character within the Central City;
5. Establish an urban design relationship between the Central City's districts and the Central City as a whole;
6. Provide for a pleasant, rich and diverse pedestrian experience for pedestrians;
7. Provide for the humanization of the Central City through promotion of the arts;
8. Assist in creating a 24-hour Central City which is safe, humane and prosperous;
9. Ensure that new development is at a human scale and that it relates to the scale and desired character of its setting and the Central City as a whole.

Staff has considered all guidelines and has addressed only those guidelines considered applicable to this project.

- A4. Use Unifying Elements.** Integrate unifying elements and/or develop new features that help unify and connect individual buildings and different areas.
- A5. Enhance, Embellish, and Identify Areas.** Enhance an area by reflecting the local character within the right-of-way. Embellish an area by integrating elements in new development that build on the area's character. Identify an area's special features or qualities by integrating them into new development.
- C4. Complement the Context of Existing Buildings.** Complement the context of existing buildings by using and adding to the local design vocabulary.

Findings: The corner blade sign is highly visible from an important public space in the heart of downtown Portland. The site is located diagonally across the intersection of SW Broadway and SW Morrison from Pioneer Square and contributes to its sense of urban enclosure. As such, the ensemble of buildings surrounding the square largely define the character of the open space. The corner tenant signage at the base of this building will create a visual anchor for the northwest corner of the iconic square.

Signage size, material, and illumination method respond to the character of the surrounding context. The height of the sign relates to the height of the base of the building. Neon lighting elements and careful detailing of the cabinet and sign face are consistent with a local sign vernacular that consist of projecting and illuminated signs. These signs help to identify the area and its commercial tenants. *These guidelines have been met.*

- A7. Establish and Maintain a Sense of Urban Enclosure.** Define public rights-of-way by creating and maintaining a sense of urban enclosure.
- A8. Contribute to a Vibrant Streetscape.** Integrate building setbacks with adjacent sidewalks to increase the space for potential public use. Develop visual and physical connections into buildings' active interior spaces from adjacent sidewalks. Use architectural elements such as atriums, grand entries and large ground-level windows to reveal important interior spaces and activities.
- B1. Reinforce and Enhance the Pedestrian System.** Maintain a convenient access route for pedestrian travel where a public right-of-way exists or has existed. Develop and define the different zones of a sidewalk: building frontage zone, street furniture zone, movement zone, and the curb. Develop pedestrian access routes to supplement the public right-of-way system through superblocks or other large blocks.
- B2. Protect the Pedestrian.** Protect the pedestrian environment from vehicular movement. Develop integrated identification, sign, and sidewalk-oriented night-lighting systems that offer safety, interest, and diversity to the pedestrian. Incorporate building

equipment, mechanical exhaust routing systems, and/or service areas in a manner that does not detract from the pedestrian environment.

- B5. Make Plazas, Parks and Open Space Successful.** Orient building elements such as main entries, lobbies, windows, and balconies to face public parks, plazas, and open spaces. Where provided, integrate water features and/or public art to enhance the public open space. Develop locally oriented pocket parks that incorporate amenities for nearby patrons.
- C7. Design Corners that Build Active Intersections.** Use design elements including, but not limited to, varying building heights, changes in façade plane, large windows, awnings, canopies, marquees, signs and pedestrian entrances to highlight building corners. Locate flexible sidewalk-level retail opportunities at building corners. Locate stairs, elevators, and other upper floor building access points toward the middle of the block.
- C8. Differentiate the Sidewalk-Level of Buildings.** Differentiate the sidewalk-level of the building from the middle and top by using elements including, but not limited to, different exterior materials, awnings, signs, and large windows.

Findings: The proposed sign will be internally illuminated to provide a limited amount of lighting to support pedestrian orientation and visibility. In addition, the sign will help to reinforce this area as a safe, active, and comfortable space for pedestrians. The design, location, and detailing of this sign is sensitive to its impact on the pedestrian environment. The height of the sign is aligned with building elements that are clearly legible from the pedestrian zone. The electrical details, with hidden conduit, also provide for a clean, well-detailed project as viewed from the sidewalk below.

The proposed location, design and scale of this sign all serve to activate an intersection. The diagonal angle of the sign engages both the adjacent streets and the adjacent public space. The diagonal direction of the proposed sign also allows it to be highly visible to pedestrians, and highlights the corner entry of the ground floor business. The proposal visually and physically enhances the pedestrian environment without creating any real or perceived obstacles. Its location demarcates the corner and indicates the presence of a destination for pedestrians at the intersection. The addition of a new sign at this corner is an appropriate connection to a common district element. *These guidelines have been met.*

- C2. Promote Quality and Permanence in Development.** Use design principles and building materials that promote quality and permanence.
- C3. Respect Architectural Integrity.** Respect the original character of an existing building when modifying its exterior. Develop vertical and horizontal additions that are compatible with the existing building, to enhance the overall proposal's architectural integrity.
- C5. Design for Coherency.** Integrate the different building and design elements including, but not limited to, construction materials, roofs, entrances, as well as window, door, sign, and lighting systems, to achieve a coherent composition.
- C10. Integrate Encroachments.** Size and place encroachments in the public right-of-way to visually and physically enhance the pedestrian environment. Locate permitted skybridges toward the middle of the block, and where they will be physically unobtrusive. Design skybridges to be visually level and transparent.
- C13. Integrate Signs.** Integrate signs and their associated structural components with the building's overall design concept. Size, place, design, and light signs to not dominate the skyline. Signs should have only a minimal presence in the Portland skyline.
- D3. Broadway Unique Sign District.** Provide opportunities for the development of large, vertically oriented, bright, and flamboyant signs that add to the unique character of this Broadway environment. Size and place signs and their structural support systems so that significant architectural or historical features of the building are not concealed or disfigured. Ensure that all signs receive proper maintenance.

Findings: The sign will draw attention to the historic building, and its unique architectural style, without obscuring any of the building's architectural elements. The proposed location will highlight the main entry, accentuate the corner of the building, and demarcate the intersection of two streets, but will not impede on

long-distance views.

The sign is appropriately scaled, designed, and placed in a manner that respects the integrity of the building and results in a cohesive design. The vertical orientation and lighting features are appropriate additions to the Broadway Unique Sign District. The sign cabinet is uniquely articulated to create visual interest from all angles. The location of the sign is respectful to the architectural integrity of the building and includes efforts to incorporate quality and coherent development to the Landmark building. The structural supports are sized and placed to avoid concealment of significant architectural features. *These guidelines have been met.*

DEVELOPMENT STANDARDS

Unless specifically required in the approval criteria listed above, this proposal does not have to meet the development standards in order to be approved during this review process. The plans submitted for a building or zoning permit must demonstrate that all development standards of Title 33 can be met, or have received an Adjustment or Modification via a land use review prior to the approval of a building or zoning permit.

CONCLUSIONS


The purpose of the Historic Resource Review process is to ensure that additions, new construction, and exterior alterations to historic resources do not compromise their ability to convey historic significance. As detailed in the findings above, this proposal meets the applicable Historic Resource Review criteria and therefore warrants approval.

ADMINISTRATIVE DECISION

Approval of Historic Resource Review for an illuminated 30 SF projecting corner blade sign on a Historic Landmark in the Central City Plan District, per the approved site plans, Exhibits C-1 through C-6, signed and dated March 6, 2018, subject to the following conditions:

- A. As part of the building permit application submittal, the following development-related conditions (B through E) must be noted on each of the four required site plans or included as a sheet in the numbered set of plans. The sheet on which this information appears must be labeled "ZONING COMPLIANCE PAGE- Case File LU 18-111036 HR." All requirements must be graphically represented on the site plan, landscape, or other required plan and must be labeled "REQUIRED."
- B. At the time of building permit submittal, a signed Certificate of Compliance form (<https://www.portlandoregon.gov/bds/article/623658>) must be submitted to ensure the permit plans comply with the Design/Historic Resource Review decision and approved exhibits.
- C. No field changes allowed.
- D. All electrical components shall be fully concealed.
- E. Sign brackets shall be installed behind the existing brick and fully concealed.

Staff Planner: Emily Hays

Decision rendered by:  **on March 6, 2018**
By authority of the Director of the Bureau of Development Services

Decision mailed March 8, 2018

About this Decision. This land use decision is **not a permit** for development. Permits may be required prior to any work. Contact the Development Services Center at 503-823-7310 for information about permits.

Procedural Information. The application for this land use review was submitted on January 23, 2018, and was determined to be complete on January 30, 2018.

Zoning Code Section 33.700.080 states that Land Use Review applications are reviewed under the regulations in effect at the time the application was submitted, provided that the

application is complete at the time of submittal, or complete within 180 days. Therefore, this application was reviewed against the Zoning Code in effect on January 23, 2018.

ORS 227.178 states the City must issue a final decision on Land Use Review applications within 120-days of the application being deemed complete. The 120-day review period may be waived or extended at the request of the applicant. In this case, the applicant did not waive or extend the 120-day review period. Unless further extended by the applicant, **the 120 days will expire on: May 30, 2018.**

Some of the information contained in this report was provided by the applicant.

As required by Section 33.800.060 of the Portland Zoning Code, the burden of proof is on the applicant to show that the approval criteria are met. The Bureau of Development Services has independently reviewed the information submitted by the applicant and has included this information only where the Bureau of Development Services has determined the information satisfactorily demonstrates compliance with the applicable approval criteria. This report is the decision of the Bureau of Development Services with input from other City and public agencies.

Conditions of Approval. If approved, this project may be subject to a number of specific conditions, listed above. Compliance with the applicable conditions of approval must be documented in all related permit applications. Plans and drawings submitted during the permitting process must illustrate how applicable conditions of approval are met. Any project elements that are specifically required by conditions of approval must be shown on the plans, and labeled as such.

These conditions of approval run with the land, unless modified by future land use reviews. As used in the conditions, the term “applicant” includes the applicant for this land use review, any person undertaking development pursuant to this land use review, the proprietor of the use or development approved by this land use review, and the current owner and future owners of the property subject to this land use review.

This decision, and any conditions associated with it, is final. It may be appealed to the Oregon Land Use Board of Appeals (LUBA), within 21 days of the date the decision is mailed, as specified in the Oregon Revised Statute (ORS) 197.830. Among other things, ORS 197.830 requires that a petitioner at LUBA must have submitted written testimony during the comment period for this land use review. Contact LUBA at 775 Summer St NE Suite 330, Salem, OR 97301-1283 or phone 1-503-373-1265 for further information.

The file and all evidence on this case are available for your review by appointment only. Please call the Request Line at our office, 1900 SW Fourth Avenue, Suite 5000, phone 503-823-7617, to schedule an appointment. I can provide some information over the phone. Copies of all information in the file can be obtained for a fee equal to the cost of services. Additional information about the City of Portland, city bureaus, and a digital copy of the Portland Zoning Code is available on the internet at www.portlandonline.com.

Recording the final decision.

If this Land Use Review is approved the final decision will be recorded with the Multnomah County Recorder.

- *Unless appealed*, the final decision will be recorded after **March 9, 2018** by the Bureau of Development Services.

The applicant, builder, or a representative does not need to record the final decision with the Multnomah County Recorder.

For further information on your recording documents please call the Bureau of Development Services Land Use Services Division at 503-823-0625.

Expiration of this approval. An approval expires three years from the date the final decision is rendered unless a building permit has been issued, or the approved activity has begun.

Where a site has received approval for multiple developments, and a building permit is not issued for all of the approved development within three years of the date of the final decision, a new land use review will be required before a permit will be issued for the remaining development, subject to the Zoning Code in effect at that time.

Applying for your permits. A building permit, occupancy permit, or development permit may be required before carrying out an approved project. At the time they apply for a permit, permittees must demonstrate compliance with:


- All conditions imposed herein;
- All applicable development standards, unless specifically exempted as part of this land use review;
- All requirements of the building code; and
- All provisions of the Municipal Code for the City of Portland, and all other applicable ordinances, provisions and regulations of the City.

EXHIBITS

NOT ATTACHED UNLESS INDICATED

- A. Applicant's Submittal
 - 1. Project Narrative
 - 2. Drawing Set
 - 3. Early Assistance Notes, dated December 20, 2018
- B. Zoning Map (attached)
- C. Plans/Drawings:
 - 1. Site Plan – Level 1 Scope
 - 2. Site Plan – Level 2 Scope (attached)
 - 3. SW Morrison Street Enlarged Elevation – Proposed
 - 4. SW Broadway Elevation – Proposed (attached)
 - 5. Sign Details
 - 6. Sign Details
- D. Notification information:
 - 1. Mailing list
 - 2. Mailed notice
- E. Agency Responses:
 - 1. Life Safety Review Section of BDS
- F. Correspondence: None
- G. Other:
 - 1. Original LU Application

The Bureau of Development Services is committed to providing equal access to information and hearings. Please notify us no less than five business days prior to the event if you need special accommodations. Call 503-823-7300 (TTY 503-823-6868).



ZONING

NORTH ↑


THIS SITE LIES WITHIN THE:
CENTRAL CITY PLAN DISTRICT
DOWNTOWN SUBDISTRICT

-  Site
-  Also Owned Parcels
-  Historic Landmark

File No.	LU 18-111036 HR
1/4 Section	3029
Scale	1 inch = 200 feet
State ID	1N1E34CC 8600
Exhibit	B Jan 26, 2018

(L.9)

(J.3)




SW BROADWAY

NOT IN SCOPE

LEASE SPACE
LEVEL 02

SCOPE OF WORK



① SITE PLAN - LEVEL 2 SCOPE
1/16" = 1'-0"

SW MORRISON ST.

Approved
 City of Portland - Bureau of Development Services
 Planner: EMMA HAYL Date: 3/6/18
 *This review applies only to the reviews requested and is subject to all applicable codes and regulations. Additional zoning requirements may apply.


EXHIBIT C-2

SITE PLAN - LEVEL 2
HISTORIC RESOURCE REVIEW - BLADE SIGN
1/22/2018

HRR2-3
715 SW MORRISON PORTLAND, OR 97205
LU 18-111036 HR

IA INTERIOR ARCHITECTS

1 1.8 2 2.7 3 3.3 4 5



GENERAL NOTE: SEE LU 17-198304 FOR PREVIOUSLY APPROVED ITEMS SHOWN.

NEW BLADE SIGN:
SEE SIGN
PACKAGE



① SW BROADWAY ELEVATION - PROPOSED
1/8" = 1'-0"

Approved
City of Portland - Bureau of Development Services
Planner: **EMMA HARRIS** Date: **3/6/18**
* This drawing applies only to the reviews requested and is subject to all conditions of approval. Additional zoning requirements may apply.

PROPOSED ELEVATION
HISTORIC RESOURCE REVIEW - BLADE SIGN
1/22/2018

IA INTERIOR ARCHITECTS

EXHIBIT C-4

HRR2-6
715 SW MORRISON PORTLAND, OR 97205
LA 18-111036 HR