

WHAT'S HAPPENING NOW

Night Week of February 11 - CANCELLED

The first early morning foundation slab pour has been delayed due to weather. Please continue to watch the webpage for the new date.

Reservoir 3 Site: Crews continue to construct drilled shafts and pour concrete slabs.

Reservoir 4 Site: Crews continue to build rebar cages, store native soils, other materials, and equipment. Previously this area was filled in, and in the future, it will be transformed into a wetland habitat. Until then it will continue to be used for storage and manufacturing to make the best use of the available space on this confined construction site.

Existing Buildings: Crews continue their work to bring them up to seismic standards and repurpose and refit them with new piping and electrical systems that will support the new reservoir.

To see recent photos and learn more about activities over the past month, including where to find a **shark fin**, click [HERE](#).

Check out the new banners in the park showing historic photos from the building of the original reservoirs and concept illustrations of the new finish reservoir [HERE](#).

FOR MORE INFORMATION

Go to www.portlandoregon.gov/water/wpreservoirs.

DID YOU KNOW?

Fire hydrant installation and maintenance is performed by the Water Bureau. The location of the hydrant was determined by the Water Bureau engineer based on the Portland Fire & Rescue criteria and the location of the nearest water main suitable for connection. On average, the Portland Water Bureau installs 50 new fire hydrants every year, and another 350 are repaired or replaced.